

[redacted]



Estimate

[redacted]

The Parish Office,
Lyth Hill Road,
Bayston Hill,
Shrewsbury,
SY3 0EW

RE: The common Slabs and Bench

Scope of Works:

- Dig out area to allow for sub base, soil to be spread around the finished area, any excess will be removed off site.
- 100mm Type 1 Clean MOT comprehensively whackered to allow for a sound compacted foundation.
- Supply and install 4.0m^2 450x450mm concrete slabs, to be laid on a full wet mortar bed of sharp sand and cement.
- Install Bench(provided by Council) using the supplied fixing kit.

Estimate Total: £995